

SURVEY & REMONUMENTATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>42N</u> R <u>4W</u> | <u>A-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED & FILED
DIANE FRAS KONICH
MACKINAC COUNTY REGISTER OF DEEDS

NOV 09 1994
AM _____ PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David B. Guthrie in a field survey on July 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: Established by Wm. Burt, G.L.O. Survey
Set wood post and referenced;
Aspen 6/S16W/35
Spruce 6/N26W/41

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 2" Iron Pipe with Brass cap.

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 8-16-94


James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Set Mackinac County Remonumentation Corner.
45/8" by 24" Iron Rod with a 3" aluminum cap stamped to identify,
set 6" below the road gravel surface.

Referenced:

- N40°W - 55.55 feet - Utility Pole
- N32°E - 35.80 feet - 3" Spruce
- S65°E - 42.84 feet - 6" Maple in clump of 4
- S84°E - 47.64 feet - 12" Aspen (Exist.)



Signed by

D. B. Guthrie

Date

Oct. 21, 1994

Surveyor's Michigan License No.

22435

11-09-94
D-0308