

SURVEY & REMONUMENTATION COMMISSION
 APR 10 1995
 MACKINAC COUNTY

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Mackinac
 (County)

Located in: Corner Code #

- 1. Public Land Survey T 42N R 4W B-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED & FILED
 DEANIE STANLEY
 NOV 09 1994
 AA
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	●												
12	31	32	33	34	35	36							
13													

I, David B. Guthrie in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845: Established by James A. Mullett, G.L.O. Survey. Set post and referenced:
 Beech 10/S69E/25
 Birch 12/N51W/12
- 1977: Survey by Larry Feindt. Set 1/2" Iron Rod by single proportion between the Northeast and Northwest Corners of Section 31.
- 1982: Survey by Thomas M. Kelly. Found 1/2" Iron Rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 3/4" Iron Rod.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-16-94

James H. Stranger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Set Mackinac County Remonumentation Corner.
 A 5/8" by 24" Iron Rod with a 3" aluminum cap stamped to identify the corner set within a monument box.

Referenced:
 S32°E - 175.00 feet - N.W. Cor. Hse. (Exist.)
 N02°W - 34.54 feet - Fence Post (Exist.)
 S75°E - 174.23 feet - Power Pole
 N15°W - 88.55 feet - 6" Apple in clump



Signed by David B. Guthrie Date Oct. 21, 1994
 Surveyor's Michigan License No. 22435

11-09-94

11-09-94

210