

1994 Mackinac County Remonumentation Corner.

SURVEY & REMONUMENTATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac
(County)

Located in:

Corner Code 44

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>42N</u> R <u>4W</u> | <u>B-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTERED & FILED
DAVID B. GUTHRIE
MICHIGAN BOARD OF LAND SURVEYORS
NOV 09 1994
MACKINAC COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie in a field survey on June 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: Established by Wm. Burt, G.L.O. Survey. Set post and referenced:
Sugar 20/N40E/24 Sugar 14/N74W/20
1977: Survey by Larry Feindt. Set a 1" Iron Pipe at the intersection of the road and a fence to the North.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found a 1" Iron Pipe in a monument box

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 8-16-94

James H. Strangor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Set Mackinac County Remonumentation Corner.
A 5/8" by 24" Iron Rod with a 3" aluminum cap stamped to identify the corner set within a monument box.

Referenced:
S71°W - 90.50 feet - Utility Pole (Exist.)
N43°E - 97.80 feet - 8" Cedar (Exist.)
N42°W - 114.75 feet - 9" Cedar (Exist.)
South - 51.67 feet - 4" Cedar
South 45.12 feet - 1" Iron Pipe



Signed by David B. Guthrie
Surveyor's Michigan License No. 22435

Date Oct. 21, 1994