

**SURVEY & REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac  
(County)

APR 10 1995

COMMISSION

Located In:

Corner Code #

- 1. Public Land Survey T 42N R 4W C-12  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECEIVED & FILED  
DEPARTMENT OF STATE  
MACKINAC COUNTY

NOV 09 1994  
AM PM  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Guthrie, in a field survey on June 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
1845: Established by James A. Mullett, G.L.O. Survey. Set post and referenced:  
Birch 20/N42E/25  
Elm 24/S89W/10  
1980: Survey by Orlando Doyle. Found 1/2" Iron Bolt  
1982: Survey by Larry Feindt. Set T-Iron  
1988: Survey by James H. Granger. Found 1/2" Iron Bolt.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1994: Found 3/4" T-Iron in Monument Box.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-16-94  
*James H. Granger*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1994: Set Mackinac County Remonumentation Corner  
A 5/8" by 24" Iron Rod with a 3" aluminum cap stamped to identify the corner set within a monument box.

- Referenced:
- N33°E - 36.48 feet - Utility Pole (Exist.)
  - S32°E - 46.72 feet - 12" Ash (Exist.)
  - S70°W - 62.20 feet - Fence Post (Exist.)
  - N75°W - 154.80 feet - Utility Pole (Exist.)
  - S18°E - 44.73 feet - Stop Sign (Exist.)

Signed by D.B. Guthrie Date Oct. 21, 1994

Surveyor's Michigan License No. 22435

D-0319