

1994 Mackinac County Remonumentation Corner.

**SURVEY & REMONUMENTATION COMMISSION**  
APR 10 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac (County) Located In: \_\_\_\_\_ Corner Code =# \_\_\_\_\_

1. Public Land Survey	T <u>42N</u> R <u>4W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED & FILED  
DAVID B. GUTHRIE  
MICHIGAN COUNTY SURVEYOR  
NOV 09 1994  
AM PM

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9		●											
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Guthrie in a field survey on June 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1845: Established by James A. Mullett, G.L.O. Survey. Set post and referenced:  
Fir 6/N45E/08  
Fir 10/S45W/25  
1983: Survey by Beryl M. Jones. Found 5/8" Iron, raised with Cabin spike and cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1/2" Iron Rod in the Centerline of a Gravel Surface Road North and South.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-16-94


*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Set Mackinac County Remonumentation Corner.  
A 5/8" by 24" Iron Rod with a 3" aluminum cap stamped to identify, set 6" below the road gravel surface.

Referenced:

N45°W - 33.80 feet - 16" Cedar (Exist.)  
S45°W - 32.20 feet - 12" Cedar (Exist.)  
S68°E - 31.80 feet - 6" Cedar (exist.)  
N47°E - 48.00 feet - 10" Cedar



Signed by D.B. Guthrie Date Oct. 21, 1994  
Surveyor's Michigan License No. 22435

D-0321