

1994 Mackinac Remonumentation Corner.

**SURVEY & REMONUMENTATION COMMISSION**  
APR 10 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mackinac  
(County)

Located In: \_\_\_\_\_ Corner Code #/

- 1. Public Land Survey T 42N R 4W \_\_\_\_\_ E-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RECEIVED & FILED  
NOV 09 1994  
MACKINAC COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


A. Description of original monument and accessories and/or subsequent restoration:  
1845: Established by James A. Mullett, G.L.O. Survey. Set Post and referenced:  
Cedar 20/N29E/17 Cedar 8/S15W/24  
1964: Survey by T.L. Jackson. Found Monument  
1973: Survey by Mary Feindt.  
1980: Survey by Orlando Doyle. Found 3/4" Iron Pipe  
1983: Survey by Beryl Jones. Found 3/4" Iron Pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1994: Found 3/4" Iron Pipe 3' South and 2' East of the intersection of Charles Moran Road and Martin Road.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 8-16-94  
*James H. Strayer*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1994: Set Mackinac County Remonumentation Corner.  
A 5/8" by 24" Iron Rod with a 3" aluminum cap stamped to identify the corner set within a monument box.

Referenced:  
North - 48.17 feet - 14" Cedar (exist.)  
N40°W - 55.65 feet - 6" Cedar  
N53°E - 66.55 feet - 15" Aspen (Exist.)  
S30°E - 83.37 feet - 24" Spruce (Exist.)



Signed by David B. Guthrie Date Oct. 21, 1994

Surveyor's Michigan License No. 22435

D-0324