

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac Located in: _____ Corner Code # _____
 (County)

1. Public Land Survey T 42N R 4W _____ L-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED & FILED
 DIANE FRANKOVICH
 MACKINAC COUNTY REGISTER OF DEEDS

NOV 7 5 1996
 AM _____ PM _____
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

I, David B. Guthrie in a field survey on June 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1845: G.L.O. Survey by J.A. Mullett - Set Post and Referenced Spruce 6 in. in Dia. for 1/4 Section Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found Railroad Spike in the centerline of Charles Moran Road.

SURVEY &
 REMONUMENTATION

MAY 20 1997

COMMISSION

ACCEPTED BY THE MACKINAC COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER P.A.
 345 OF 1990 AT A MEETING
 HELD ON 8-20-96

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Replaced a Railroad Spike with a 5/8" x 24" Iron Rod with an Aluminum Cap stamped to identify the corner.
 Referenced: S20°W - 8" Cedar - 41.35 Feet
 S27°E - 8" Cedar - 49.05 Feet
 S43°E - 4" Cedar - 47.52 Feet
 N27°W - 6" Cedar - 47.32 Feet



Signed by David B. Guthrie

Date Oct. 2, 1996

Surveyor's Michigan License No. 22435