

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 43N N.R. 1W


Mackinac COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 21-22-27-28

CORNER MONUMENT 1 1/4" X 30" iron pipe

DATE MONUMENT PLACED AND WITNESSED 8-5-69

WITNESSES TO CORNER..... 22" W. Spruce (NBT) S21°E 102.4'



8" W. Spruce (NBT) N89°E 23.7'

SW corner of house N86°E 118.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed midway between Sec. Cors; one mile north and one mile south and in center of N.-S. County Road.
Position agrees with calls of the original notes, to a stream to North and West.
Found no evidence of original corner.
Corner lies 3.4' south of south edge of house to east of road.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler REGISTERED LAND SURVEYOR DATE 1-20-71