

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

~~Chippewa Co.~~

2 Corners.

MANU. 000

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.	T. 43 N. 1 E. SW. R. 1	F-9, E-9
2. PROPERTY CONTROLLING IN SECTION.	T. N. S. R.	E. W.
3. MISCELLANEOUS PROPERTY IN SECTION.	T. N. S. R.	E. W.
4. LOT NO. , RECORDED PLAT		
5. PRIVATE CLAIMS.		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, *Gerald L. Wiggins*, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-25, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

F-9 North 1/4 Corner of Section 28. OBT'S: Hemlock 10", N38°W, 18 lks. & Hemlock 10", S22°W, 21 lks.

E-9 N.W. Corner of Section 28. OBT'S: A Cedar 15" For Corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-9 Corner set M.P.O.L. between N.W. Corner and N.E. Corner of Section 28.

E-9 Corner set in Cedar Stump Bottom. Proportionate measure to streams North, South, and East fit original measure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument at both corners.

F-9 6" R. Maple, South, 63.6'  
6" R. Maple, North, 9.95'  
4" R. Maple, N31°E, 27.3'  
8" Cedar, S88°E, 14.1'

E-9 10" H. Maple, S3°E, 44.0'  
10" Cedar, S80°E, 41.9'  
5" R. Maple, S58°W, 20.3'  
8" H. Maple, N11°E, 20.1'

SIGNED BY

*Gerald L. Wiggins*  
Gerald L. Wiggins

DATE

9-9-87

SURVEYOR'S MICHIGAN REGISTRATION NO.

23521

FOR STATE AND UNITED STATES AGENCIES:

