

14

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 1W G11
T 43N R 1W G9

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property In Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Aug 21 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	16			17			18		15		14		13
7													
8	19			20			21		22		23		24
9							●						
10	30			29			28		27		26		25
11							●						
12	31			32			33		34		35		36
13													


A. Description of original monument and accessories and/or subsequent restoration:
(G11) Corner common to Sections 27-28-33-34. Corner reestablished in 1969 by Billy D. Buckler, ALS: "This corner placed in intersection of county road, in all four directions. found no evidence of corner here. Used this corner to re-establish a corner, one mile north. Corner monument: 5/8" iron rod, driven in intersection, witnesses to corner: Stop sign N27W 46.7', Stop sign N69E 55.8', Stop sign, S20E 58.8', Stop sign S65W 62.9'".
(G9) Corner common to Sections 21-22-27-28. Corner reestablished in 1969 by Billy D. Buckler, ALS: "This corner placed midway between Sec. Cors; one mile north and one mile south and in center of N.-S. County Road. Position agrees with calls of the original notes, to a stream to North and West. Found no evidence of original corner. Corner monument: 1 1/4" x 3/4" iron pipe. Witnesses to corner: 22' W. Spruce S21E 102.4', 8" W. Spruce N89E 23.7', SW corner of house N65E 118.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G11) Recovered the 1969 monument, as described, in good condition, buried in the intersections of county roads leading N, S, E, and W. All of the 1969 Stop sign witnesses have been replaced. Left the monument in place and made four new witnesses as described below. Corner recovered and witnessed by T.Stark and D.Lampela, Newberry District Office.
(G9) Recovered the 1969 monument as described, in good condition, and at record bearing and distance from the 8" Spruce and house witnesses noted above. The third 1969 accessory was not recovered. Left the monument in place, made new NBT markings and placed measuring nail in the 8" (now 14") Spruce, and marked two new witnesses as described below. Corner recovered and witnessed by T.Stark and D.Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G11) Found 5/8" dia. iron rod. Placed measuring nails with tags in the following witness objects:
P. Pole FT4-102C-1 S25W 126.6'
P. Pole FT4-102-40 S15E 139.7'
P. Pole (no marking) N21E 192.1'
Wood Stop sign post N25W 49.15'
Bearings are magnetic.
(G9) Found 1 1/4" iron pipe. The 1969 witnesses:
14" W. Spruce S89E 24.2' "NBT"
SW corner of house N65E 118.3'
Blazed, scribed and set measuring nails in the following:
12" W. Spruce S81E 75.75' "NBT"
6" W. Spruce S67E 33.35' "NBT"
Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No.

33986

Date

1-28-97

For the Michigan Department of Natural Resources - Forest Management Division