

12

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac	Located In:	Corner Code #
(County)		
1. Public Land Survey	T. 434 R. 1W	C8
	T. R.	
	T. R.	
	T. R.	
2. Property Controlling In Section	S. 20 T. 434 R. 1W	15
	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
	S. T. R.	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

15 Sep 03 1996
C8 Jul 08 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C8) Quarter corner common to Sections 19-20. Corner established in 1845 by James Mullett: "...40.00 Set Quarter Section Post. Cedar 15 S70E 12, Fir 15 S39W 26...44.00 Spring Brook 10 C. East...".
(15-Sec. 20) West 1/16 corner between Sections 20-29. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C8) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record between Section corners 2616.39 ft. north and south. The corner falls in what appears to be an old camp clearing. The Spring Brook noted in the original record is not identifiable. Five or six small streams cross the line between Section 19-20 between 320' and 610' north of the reestablished corner. At the position for the corner, I placed a 1"10 x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office.
(15-Sec. 20) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of true bearing between Section corner 1336.79' west and quarter corner 1336.79' east. At the position for the corner, I placed a 1"10 x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C8) Set 1" pipe with 4" MDNR cap.	(15) Set 1" iron pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails	Blazed, scribed, and set measuring nails
in the following:	in the following:
6" Spruce S09W 26.45' 1/4S NBT	5" Balsam S87W 4.85' *W1/16 BT
8" Balsam S45E 12.0' 1/4S NBT	5" Maple S25W 12.85' *W1/16 BT
16" W. Birch N27W 35.6' 1/4S NBT	4" Maple S25E 14.9' *W1/16 BT
4" W. Birch S49W 20.15' 1/4S NBT	5" Maple S81E 3.7' *W1/16 BT
Placed a 5" squared and scribed cedar post adjacent. Bearings are magnetic.	Placed a 4" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 1-28-97

For the Michigan Department of Natural Resources - Forest Management Division