

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 43N R 1W F8

T R _____

T R _____

T R _____

2. Property Controlling
in Section

S 21 T 43h R 1W 8

S T R _____

3. Miscellaneous
Property In Sec.

S T R _____

S T R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Aug 21 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
(F8) Center of Section 21. Corner not established in the original survey. Found no subsequent record.
(8-Sec. 21) Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F8) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/4 corners 2623.44' North, 2641.44' East, 2620.18' South, and 2649.06' West. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum WDNR tablet, appropriately stamped. From the corner monumented, an E-W cutting edge is approx. 30' South, and a N-S cutting edge is approx. 100' East. Corner placed and witnessed by T. Stark and D. Lampela, Newberry District Office.

(8-Sec. 21) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1324.03' West and Center of Section 1324.03' East. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum WDNR tablet, appropriately stamped. From the corner, the NE corner of a clear-cut is approximately 33 ft. South. Corner placed and witnessed by T. Stark and D. Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F8) Set 1" pipe with 4" WDNR cap.	(8) Set 1" pipe with 4" WDNR cap.
Blazed, scribed, and set measuring nails in the following:	Blazed, scribed, and set measuring nails in the following:
14" W. Birch N46E 22.6' "CS BT"	5" W. Birch S12E 18.35' "W1/16 BT"
14" Cedar S74E 77.15' "CS BT"	5" Balsam S70W 11.4' "W1/16 BT"
14" Cedar S54E 52.55' "CS BT"	8" Spruce S52W 14.6' "W1/16 BT"
4" Balsam N63W 36.5' "CS BT"	6" Spruce N54W 13.8' "W1/16 BT"
Placed a 6" Squared and scribed cedar post adjacent. Bearings are magnetic.	Placed a 3" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 1-28-97

For the Michigan Department of Natural Resources - Forest Management Division