

10

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MacKINAC

(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 1W E8

T R _____

T R _____

T R _____

2. Property Controlling
in Section

S 20 T 43N R 1W 7

S T R _____

3. Miscellaneous
Property in Sec.

S T R _____

S T R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sep 13 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E8) Quarter corner common to Sections 20-21. Corner established in 1845 by James Mullett; ...40.00 Set quarter section post. Cedar 8 S68E 10, do 8 N36W 12".

(7-Sec. 20) North 1/16 corner between Sections 20-21. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E8) Original post and accessories not recovered. There are several old cedar stumps in the area, all in advanced stages of decay, but none will match with the record. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record between Section corners 2614.10' north and south. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MONR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office.

(7-Sec. 20) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Section corner 1307.02' North, and Quarter corner 1307.02' South. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MONR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E8) Set 1" pipe with 4" MONR cap. Blazed, scribed, and set measuring nails in the following:

12" Tamarack N45E 5.45' "1/4S NBT"

12" Tamarack S10E 20.75' "1/4S NBT"

5" Tamarack N88W 13.4' "1/4S NBT"

12" Tamarack S47W 17.55' "1/4S NBT"

Placed a 4" squared and scribed post adjacent. Bearings are magnetic.

(7) Set 1" pipe with 4" MONR cap. Blazed, scribed, and set measuring nails in the following:

12" W. Birch S15E 8.95' "N1/16 BT"

8" Balsam S84W 14.1' "N1/16 BT"

10" Maple N78W 29.15' "N1/16 BT"

8" Balsam N62W 22.1' "N1/16 BT"

Placed a 4" squared and scribed post adjacent. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

1-28-97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division