

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 1W E7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property In Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sep 04 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7					●								
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration.

(E7) Corner common to Sections 16-17-20-21. Corner reestablished in 1964 by Neal Sperhake, RLS, by double proportionate measurement to the original record between corners 80.31 ch. East, 160.59 ch. West, 79.53 ch. North, and 153.07 ch. South (Sperhake's meas.). Corner monument: 1" IDx36" galvanized iron pipe capped with a stamped aluminum Kimberly-Clark Corp. tablet. Witnesses to corner: Balsam 8 N79E 9 links, Cedar 7 N79W 59.5 links, Balsam 7 S61W 29 links, Spruce 7 S55E 55 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(E7) Recovered the 1964 monument, as described, in good condition, and at record bearing and distance from the two remaining 1964 witnesses, a 7' high balsam snag, with markings, and a 12" Cedar, with overgrown markings. An old wooden post stands adjacent to the monument. I determined the distances East and South to monumented corners to be 80.274 ch. and 158.939 ch. respectively. Accepted the monument as a careful and faithful reestablishment of the position of the corner. Left the monument in place, made new marks and set a measuring nail in the 1964 Cedar, and marked three new accessories as described below. Corner recovered and re-witnessed by T. Stark and D. Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(E7) Found 1" pipe with Kimberly-Clark Corp. cap. Blazed, scribed, and set measuring nails in the following:
12" Cedar N70W 38.95' "S17"
8" Balsam N55W 16.3' "S17 NBT"
5" Balsam S22W 21.7' "S20 NBT"
8" Balsam N10E 20.7' "S16 NBT"
Placed a 3" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

1-28-97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division