

**SURVEY &
REMONUMENTATION**

JAN 21 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Mackinac County Remonumentation Corner

For corners in

<u>Mackinac</u>	Located in:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>1W</u>	<u>B-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1998
AM _____ PM _____
2|3|4|5|6|7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

I, Larry R. Rogers in a field survey on December 21, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2	W	1	
3													
4		7		8		9		10		R	11		12
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
(B-1) North 1/4 Corner of Section 6, Township 43 North, Range 1 West.
Original corner was placed in 1840 by W.A. Burt. In 1912 the Chippewa County Surveyor did a breakdown of Section 31, Township 44 North Range 1 West. In 1994 Larry R. Rogers re-established corner position on line between Southwest and Southeast corners of Section 31 at a proportionate distance based on the 1912 County Surveyor notes and recorded in Chippewa County Corner Records as part of the Chippewa County Remonumentation Program.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(B-1) North 1/4 Corner of Section 6, Township 43 North, Range 1 West.
This corner is being re-established as part of the Mackinac County Remonumentation Program.
Recovered 3/4" iron with "Chippewa County Remonumentation Corner" cap as recorded by Rogers in 1994. Corner falls on the extension of a fence line to the North and 2 feet North of the centerline of Townline Road. Recovered four "Rogers" witnesses. Placed monument box over corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(B-1) North 1/4 Corner of Section 6, Township 43 North, Range 1 West.
Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation Corner" cap. Corner falls on range of fence to North, 2 feet North of centerline of Townline Road, and 17 feet West of range of fence to South.

Witnesses:

Utility Pole (PD3/70/65)	N72°E	79.34 feet
Corner Fence Post	S19°E	42.55 feet
Fence Post	S24°W	56.18 feet
End Fence Post	N16°W	55.06 feet

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 12-04-98 WEM



Signed by [Signature] Date 23 DEC 1998

Surveyor's Michigan License No. 29251

NOTE: Bearings are magnetic compass bearings not corrected for declination. Distances are to a nail in side of witness object unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995