

SURVEY & REMONUMENTATION

JAN 21 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 Mackinac County Remonumentation Corner

For corners in

Mackinac

Located In:

Corner Code #

1. Public Land Survey

T 43N R 1W

C-1

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED & FILED
 DIANE FRANKOVICH
 MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1998

AM _____ PM _____
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

I, Larry R. Rogers in a field survey on December 21, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3			2		1	
3													
4		7	8	9	10					11		12	
5													
6		16	17	18	15					14		13	
7													
8		19	20	21	22					23		24	
9													
10		30	29	28	27					26		25	
11													
12		31	32	33	34					35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
C-1 Northeast Corner of Section 6, Township 43 North, Range 1 West.

Original corner was placed in 1840 by W.A. Burt. In 1912 the Chippewa County Surveyor did a breakdown of Section 31, Township 44 North, Range 1 West. In 1994 Larry R. Rogers found a 5/8" iron 18" below grade. Distance to South 1/4 corner of Section 31 was within 0.5 feet of 1912 County Surveyor distance. Accepted corner position as found and set 3/4" x 24" iron with plastic remonumentation cap above found corner to bring to surface of road. Corner was recorded in the Chippewa County Corner Records as part of the Chippewa County Remonumentation Program.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-1 Northeast Corner of Section 6, Township 43 North, Range 1 West.

This corner is being re-established as part of the Mackinac County Remonumentation Program. Recovered 3/4" iron as recorded by Rogers in 1994. Corner had been paved over. Also recovered two 1994 witnesses. Accepted corner position as found and placed monument box over corner. Added new plastic "Chippewa County Remonumentation Corner" cap and established two new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-1 Northeast Corner of Section 6, Township 43 North, Range 1 West.

Corner is a 3/4" iron with plastic "Chippewa County Remonumentation Corner" cap in a monument box. Corner falls 1.5 feet North of centerline of Townline Road and 2 feet West of centerline of McCabe Road to the North.

Witnesses:

Utility Pole (PD3/70/57) N49°E 43.89 feet
 Corner Fence Post S37°E 69.33 feet
 Burr Oak 14" S65°W 44.54 feet
 Corner Fence Post N40°W 49.34 feet

ACCEPTED BY THE MACKINAC COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER P.A.
 345 OF 1990 AT A MEETING
 HELD ON 12-04-98 NEH



Signed by _____ Date 23 Dec 1998

Surveyor's Michigan License No. 29251

NOTE: Bearings are magnetic compass bearings not corrected for declination. Distances are to a nail in side of witness object unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995