

1995 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac (County) Located In: Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>1W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED & FILED
DIANE FRANKOVICH
 MACKINAC COUNTY REGISTER OF DEEDS

NOV - 7 1995
 AM _____ PM
 7|8|9|10|11|12|1|2|3|4|5|6

A

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	0		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, David B. Guthrie a field survey on 8/2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845: Established by J.W. Mullett, G.L.O. Survey - Set post and referenced Hemlock 20 - S76E - 40 / Birch 30 - N77W - 21

1994: Survey by Ronald Bischer - Found 1 1/2" Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 1 1/2" Iron Pipe

SURVEY & REMONUMENTATION

DEC 01 1995

COMMISSION

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-18-95

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced 1 1/2" Iron Pipe with a 5/8"x24" Iron Rod with a 3" Aluminum Cap stamped to identify the corner. The corner was set 6" below the road surface.

- Referenced - (Exist.) N39°W - Utility Pole - 45.55 Feet
- (Exist.) S82°W - 14" Spruce - 49.80 Feet
- (Exist.) S48°E - 5" Balsam - 55.95 Feet
- (Exist.) East - 1/2" Iron Rod - 33.00 Feet
- S86°E - 6" W. Birch - 38.53 Feet

Signed by David B. Guthrie
 Surveyor's Michigan License No. 22435

Date 9/19/95

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971, REVISED MAY 14, 1976, REVISED JAN 1995

D - 0378

