

SURVEY & REMONUMENTATION

MAR 13 1998 1997 Mackinac County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**
Mackinac
(County)

Located In:

Corner Code #

- | | | | |
|---|--------------|-------------|---------------------------|
| 1. Public Land Survey | T <u>43N</u> | R <u>1W</u> | Corner Code # <u>G-11</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous
Property in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

RECEIVED & FILED
DIANE PEAL KOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1997

AM 3PM
718/912-1111

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie, in a field survey on July 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:**
1845: G.L.O. Survey by J.H. Mullett - Set Post and Referenced -
Sugar 20 / N70W / 21
Sugar 18 / S76E / 13

- 1969: Survey by Billy D. Buckler - Placed a 5/8" Iron Rod at the intersection of the County road. Referenced -
N27°W - Stop Sign - 46.7'
N69°E - Stop Sign - 55.8'
S20°E - Stop Sign - 58.8'
S69°W - Stop Sign - 62.9'
Recorded in Book 2, Page 635, Land Cor. Records. (Cont'd on other side)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1997: Remonumentation survey by R.S. Scott Associates, Inc.
Found Railroad spike at road intersection.
Referenced -
(Exist.) S26°W - Utility Pole - 126.85'
(Exist.) S18°E - Utility Pole - 139.65'
(Exist.) N23°W - Stop Sign - 49.20'
N58°E - 8" Red Pine - 49.15'

ACCEPTED BY THE MACKINAC COUNTY
SURVEY FEER GROUP AS THE
OFFICIAL CORNER UNDER PA.
345 OF 1990 AT A MEETING
HELD ON 11-21-97

This corner position is compatible with County and local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1997: Placed 3" Mackinac County Cap stamped to identify the corner over 1/2" Iron Rod in Monument Box.
Referenced -
S26°W - Utility Pole - 126.85'
S18°E - Utility Pole - 139.65'
N23°W - Stop Sign - 49.20'
N58°E - 8" Red Pine - 49.15'



Signed by David B. Guthrie

Date 12-19-97

Surveyor's Michigan License No. 22435

SURVEY &
REMONUMENTATION

MAR 13 1998

SECTION

(Cont'd from other side)

A. 1996: Survey by Stephan J. Szyszkoski - Recovered 5/8" Iron Rod placed by Billy D. Buckler in 1969.

Referenced -

S26°W - Utility Pole - 126.8'

S15°E - Utility Pole - 139.7'

N21°E - Utility Pole - 192.1'

N25°W - Stop Sign - 49.15'

L.C.R.C. Recorded in Book E, Page 129.