

**SURVEY &
REMONUMENTATION**

JAN 21 1999

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

Mackinac County Remonumentation Corner

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T43N R01W	H-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1998

AM PM
1|2|3|4|5|6|7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

I, Neil E Hill, in a field survey on 12-21-98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

T43N R1W

A. Description of original monument and accessories and/or subsequent restoration:

1845 GLO Notes William A Burt	20" Sugar	N 44 E	21 lks
	4" Sugar	S 15 W	21 lks
1994 R Bischer	10" Maple	N 05 W	59.30 ft
Fd 1/2" Rod	8" J Pine	S 36 E	50.40 ft
Liber D, Page 264	3" J Pine	S 38 W	69.05 ft
	10" Maple	N 46 E	65.50 ft

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER PA.
345 OF 1990 AT A MEETING
HELD ON 12-04-98 NEH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Fd 1/2" rod and 4 witnesses
Accepted corner location

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" bar in E-W road

12" Maple	N 05 W	59.40'
8" J Pine	S 25 E	20.29'
3" J Pine	S 38 W	69.05'
12" Maple	N 50 E	65.56'
12" J Pine	S 10 E	50.00'

Bearings are compass bearings, corrected for declination, all distances are to a double-headed nail in the side of the witness object unless otherwise noted.



Signed by Neil E. Hill P.S.

Date 12-29-98

Surveyor's Michigan License No. 27447