

JAN 21 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Mackinac County Remonumentation Corner

For corners in

Mackinac County

Located in:

Corner Code #

- 1. Public Land Survey T42N R01W
- T43N R01W
- T R
- T R
- T R
- T R
- T R
- T R

H-1  
H-13 ✓

- 4. Lot No. , Recorded Plat
- 5. Private Claims

RECEIVED & FILED  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1998

AM PM  
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2			1
3													
4	7		8		9			10					12
5													
6	18		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

I, Neil E Hill, in a field survey on 12-21-98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845 GLO Notes James Mullett 10" Sugar N 40 E 42 lks
- 12" Sugar N 46 W 9 lks
- 1991 K Waters 18" Basswood S 25 W 23.08'
- Set 1/2' re-rod Cap # 33142 14" Maple N 57 W 12.88'
- Liber D, Page 264 8" Maple N 04 E 21.60'
- 8" Maple N 52 E 11.58'

1994 R Bischer Found Re-rod Cap # 33142

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-11-98 NEH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998 Fd 1/2 Rerod Cap # 33142 and 3 witnesses (nails almost grown over)
- Accepted corner location
- Placed 4" Alum. remonumentation cap

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" re-rod with 4" Alum. remonumentation cap  
Corner is Approx 300 feet West of South edge of corn field

- 18" Basswood S 25 W 23.08'
- 14" Maple N 57 W 12.88'
- 8" Maple N 04 E 21.60'
- 8" Maple N 52 E 11.58'



Bearings are compass bearings, corrected for declination, all distances are to a nail in the side of the witness object unless otherwise noted.

Signed by Neil E. Hill P.S.

Date 12-29-98

Surveyor's Michigan License No. 27447