

1995 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>43N</u> R <u>1W</u>	<u>T-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED & FILED
 DIANE FRAD KOVICH
 MACKINAC COUNTY REGISTRE OF DEEDS

NOV - 7 1995
 AM _____ PM
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie a field survey on 8/2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845: Established by J.W. Mullett, G.L.O. Survey - Set post and referenced Spruce 10 - N41E - 11 / Cedar 20 - S67W - 20
- 1979: Survey by Richards and Assoc. - Set 5/8" Iron Rod at road intersection
- 1989: Survey by George J. Avendt - Found 1/2" Iron Rod at road intersection
- 1994: Survey by Ronald Bischer - Found 1/2" Iron Rod in Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1995: Found 1/2" Iron Rod in Monument Box at the road intersection.

SURVEY &
 REMONUMENTATION

DEC 1 1995

COMMISSION

ACCEPTED BY THE MACKINAC COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER P.A.
 345 OF 1990 AT A MEETING
 HELDON 9-18-95

James H. Grayson

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: Placed a 3" Aluminum Cap stamped to identify the corner on a 1/2"x24" Iron Rod in a Monument Box.
- Referenced - (Exist.) N33°W - Fence Post - 52.58 Feet
- (Exist.) N50°E - Fence Post - 64.34 Feet
- (Exist.) S39°W - Utility Pole - 61.38 Feet
- (Exist.) South - 18" Spruce - 103.55 Feet

Signed by *David B. Guthrie* Date 9/19/95

Surveyor's Michigan License No. 22435

D-0379

