

**SURVEY &  
REMONUMENTATION**

JAN 21 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Mackinac County Remonumentation Corner

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T43N R01W	I-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

**RECEIVED & FILED**  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS  
DEC 31 1998  
AM P:1  
2|2|3|4|5|6|7|8|9|10|11|12|13|14|15|16

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

*T43N R01W*

I, Neil E Hill, in a field survey on 12-21-98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 GLO Notes William A Burt	20" Sugar	S 25 W	35 lks
	8" Sugar	N 33 E	38 lks
1994 R Bischer	24" Maple	S 65 W	69.60 ft
Fd ¾" Pipe	12" Maple	N 40 W	63.10 ft
Liber D, Page 265	Fence Cor	N 45 E	46.15 ft
	Phone Box	S 38 E	46.50 ft

**ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 12-04-98 NEH**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Fd ¾ pipe and 4 witnesses 12" below grade of road  
Accepted corner location  
Raised corner with ½" re-bar placed inside pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a ½" re-bar in E-W road

24" Maple	S 70 W	69.75'
12" Maple	N 40 W	63.08'
14" Oak	N 50 E	45.38'
12" Maple	N 20 W	78.00'



Bearings are compass bearings, corrected for declination, all distances are to a double-headed nail in the side of the witness object unless otherwise noted.

Signed by Neil E. Hill P.S.

Date 12-29-98

Surveyor's Michigan License No. 27447