

SURVEY & REMONUMENTATION

JAN 21 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mackinac County Remonumentation Corner

For corners in

| | | |
|------------------------------------|-------------|---------------|
| Mackinac County | Located in: | Corner Code # |
| 1. Public Land Survey | T42N R01W | J-1 |
| | T43N R01W | J-13 ✓ |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. , Recorded Plat | | |
| 5. Private Claims | | |

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1998

AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Neil E Hill, in a field survey on 12-21-98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|------------------------------|-------------|--------|--------|
| 1845 GLO Notes James Mullett | 8" Tamarack | N 72 E | 7 lks |
| | 16" Birch | N 44 W | 11 lks |
| 1970 DNR Billy Buckler | 12" Cedar | S 62 E | 30.5' |
| Set 1" pipe and DNR cap | 7" Cedar | Due N | 27.5' |
| From original BT | | | |
| Liber 2, Page 638 | | | |
| 1992 S Kass | 7" Cedar | Due N | 27.10' |
| Fd 1" pipe and broken cap | 20" Hemlock | S 56 E | 24.50' |
| Liber D, Page 163 | 14" Hemlock | S 35 W | 24.54' |
| | 8" Cedar | N 59 E | 27.63' |

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER PA. 345 OF 1990 AT A MEETING HELD ON 12-11-98 NEH


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Fd 1" pipe, broken cap and 4 witness trees
Original Y Birch BT is now up-rooted and down to NW
Accepted corner location

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is 1" pipe with a broken DNR cap
Corner is on North edge of E-W snowmobile trail
Corner is partially protected by rootball of downed BT

| | | | |
|-------------|--------|--------|-------|
| 7" Cedar | Due N | 27.10' | (Old) |
| 20" Hemlock | S 56 E | 24.50' | (Old) |
| 14" Hemlock | S 35 W | 24.54' | (Old) |
| 8" Cedar | N 59 E | 27.63' | (Old) |



Bearings are compass bearings, corrected for declination, all distances are to a 20 penny nail in the side of the witness object unless otherwise noted.

Signed by Neil E. Hill P.S.

Date 12-29-98

Surveyor's Michigan License No. 27447