

1995 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac Located In: _____ Corner Code # _____
 (County)

RECEIVED & FILED
 DIANE FRANKOVICH
 MACKINAC COUNTY REGISTER OF DEEDS

NOV - 7 1995
 AM 11:10 PM
 7|8|9|10|11|12|1|2|3|4|5|6

- | | | |
|--------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>43N</u> R <u>1W</u> | <u>K-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie a field survey on 8/2, 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845: Established by J.W. Mullett, G.L.O. Survey, Set post and referenced
 Fir 4 - S64W - 14 / Tank. 8 - N73E - 10

1993: Survey by Ronald Bischer - Found 1/2" Iron Rod

1994: Bridge Design Survey by R.S. Scott Assoc. - Found 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 1/2" Iron Rod

SURVEY &
 REMONUMENTATION

DEC 01 1995

COMMISSION

ACCEPTED BY THE MACKINAC COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER P.A.
 345 OF 1990 AT A MEETING
 HELD ON 9-18-95

James H. Granger



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Placed a 3" Aluminum Cap stamped to identify the corner on a 1/2"x24" Iron Rod set 6" below the road surface.

- Referenced - (Exist.) N25°W - Utility Pole - 60.62 Feet
 (Exist.) N27°E - Utility Pole - 72.86 Feet
 (Exist.) N06°E - Bridge Sign - 78.00 Feet
 (Exist.) S88°E - Fence Post - 59.06 Feet
 (Exist.) N50°W - N.E. Cor. Hse. - 102.87 Feet
 (Exist.) N75°W - S.E. Cor. Hse. - 91.04 Feet

Signed by

D.B. Guthrie

Date

9/19/95

Surveyor's Michigan License No. 22435

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN, 1983

D-0381