## SURVEY & REMONUMENTATION

JAN 21 1999

## SECTION

4 Lot No. 5. Private Claims

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in					
Mackinac County	Locat	Located in:		Corner Code #	
Public Land Survey		T43N T T T	R01W R R R	K-12	
Property Controlling in Section	S S	T T	R R		
Miscellaneous Property in Sec.	S S	T T	R R		

, Recorded Plat

RECEIVED & FILED DIANE FRANKOVICH

DEC 3 1 1998 知為 AN 21819119111112111213141516


Register of Deeds Stamp & File Number

I, Neil E Hill, in a field survey on 12-21-98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 GLO Notes William A Burt	20" Sugar	N 51 W	39 lks
	10" Sugar	S 44 E	20 lks
1992 Stanley Kass Fd 1 ¼" Pipe Liber D, Page 162	32" H Maple 18" H Maple 14" Twin Maple 12" H Maple	N 46 E N 44 W N 76 W N 30 W	23.84 ft 62.08 ft 60.70 ft 67.84 ft



ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING 12-11-98 HELD ON NEH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Fd 1/2 rebar with cap (H Goodwin) Accepted corner location Placed 4" Alum, remonumentation cap

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" rerod with 4" Alum, remonumentation cap Corner is in intersection of N-S road and West 2 track

0071111	N. 40 E	00.00
36" H Maple	N 46 E	23.89'
18" H Maple	N 44 W	62.13
14" Twin Maple	N 76 W	60.75
12" H Manle	N 30 W	67.89



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Date

Surveyor's Michigan License No.