

**SURVEY &  
REMONUMENTATION**

**JAN 21 1999**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Mackinac County Remonumentation Corner**

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T43N R1W T43N R1E	<b>M-2</b> A-2 (Same corner Chippewa County)
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

**RECEIVED & FILED**  
**DIANE FRANKOVICH**  
 MACKINAC COUNTY REGISTER OF DEEDS

**DEC 30 1998**

AM PM  
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

**ACCEPTED BY THE MACKINAC COUNTY  
 SURVEY PEER GROUP AS THE  
 OFFICIAL CORNER UNDER P.A.  
 345 OF 1990 AT A MEETING  
 HELD ON 11-20-98 NEH**

I, Keith R. Waters, in a field survey on November 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2 ¼ Corner Common to Section 1, T43N, R1W & Section 6, T43N, R1E

1840 - Original corner established by William A. Burt.

Highway Department notes indicate corner 2.1' west of the centerline of Highway M-129.

1982 - LCRC, liber 5, page 227, Chippewa County corner records. William L. Karr, P.S. 27450, found no evidence of corner. Reestablished corner on line with fences east and west, 77.1' west of a concrete R.O.W. monument on the east side of M-129. Distances to section corners north and south match Highway Department notes.

Witnesses: P. Pole (E44), N31°E 127.74' - P. Pole (E43), S43°E 102.33' - Conc. R.O.W. mon., EAST 77.10'.

1991 - MDOT notes corner found and witnessed prior to road construction.

1992 - LCRC, liber 7, page 358, Chippewa County corner records. Neil E. Hill, P.S. 27447, reset ½" iron in a monument box after road construction from 1991 witnesses. Witnesses: R.O.W. marker, EAST 76.11' - Power Pole, N31°E 127.23' - Power Pole (E80), S45°W 95.77' - Power Pole (E81), N27°W 140.88'.

1994 - LCRC, liber 8, page 308, Chippewa County corner records. Keith R. Waters, P.S. 33142, found iron #27447 in a monument box and all record witness objects as called for in 1992 LCRC. Witnesses same as previous LCRC.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Mackinac County Remonumentation Program.

Found a ½" iron with cap #27447 in a monument box and all record witness objects from 1994 LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a ½" iron with cap #27447 in a monument box at the corner location. Witnesses:

Nail and MDOT reference tag in Power Pole, N31°E 127.23'

Nail and MDOT reference tag in Power Pole (E80), S45°W 95.77'

Nail and MDOT reference tag in Power Pole (E81), N27°W 140.88'

Top center of concrete right of way monument (broken off), EAST 76.11'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Keith R. Waters

Date 12-23-98

Surveyor's Michigan License No. 33142