

**SURVEY & REMONUMENTATION**

**JAN 21 1999**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Mackinac County Remonumentation Corner**

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T43N R1W T43N R1E	<b>M-3</b> A-3 (Same corner Chippewa County)
2. Property Controlling in Section	S S	T R T R
3. Miscellaneous Property in Sec.	S	T R
4. Lot No. , Recorded Plat		
5. Private Claims		

**RECEIVED & FILED**  
**DIANE FRANKOVICH**  
 MACKINAC COUNTY REGISTER OF DEEDS

**DEC 30 1998**  
 AM PM  
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 11-20-98 NEH

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Keith R. Waters, in a field survey on November 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3 Corner Common to Secs. 1 & 12, T43N, R1W & Secs. 6 & 7, T43N, R1E

- 1840 - Original corner established by William A. Burt.
- 1982 - LCRC, liber 5, page 229, Chippewa County corner records. William L. Karr, P.S. 27450, found a 2" brass plug in bridge, set by State Highway Department. Witnesses: Centerline of M-129, EAST 1.24' - Power pole (129), N61°E 53.12' - Corner of concrete guard rail supports, N62°W 18.78' & N59°E 20.77'.
- 1993 - LCRC, liber 8, page 319, Chippewa County corner records. Keith R. Waters, P.S. 33142, found 2" brass plug in bridge and all record witnesses per previous LCRC. Corner being perpetuated as part of the Chippewa County Remonumentation Program.
- 1996 - LCRC, liber 10, page 251, Chippewa County corner records. Gary E. Koepke, P.S. 26458, corner found in 1994 and preserved prior to bridge construction. Reestablished the corner in 1996 after bridge construction. Set a 2" stamped brass disk in the concrete bridge deck. Witnesses:  
 "V" notch in top of metal guard rail post, N28°10'35"E 39.06'  
 USGS stamped brass disk "TT 68 S 1929" in 6" square concrete monument, N49°50'46"E 46.03'  
 Drill hole in top center of concrete right-of-way marker, S88°50'04"E 51.40'  
 Drill hole in top center of concrete right-of-way marker, N89°35'26"W 74.00'  
 "V" notch in top of metal guard rail post, N23°45'21"W 38.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Mackinac County Remonumentation Program. Found a 2" brass plug in bridge and all record witness objects from 1996 LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Found a stamped 2" diameter brass plug in bridge over Munuscong River at the corner location, which falls in Highway M-129. Witnesses:  
 "V" notch in top of metal guard rail post (ninth post north of bridge), N28°10'35"E 39.06'  
 USGS stamped brass disk "TT 68 S 1929" set in 6" square concrete monument, N49°50'46"E 46.03'  
 Drill hole in top center of concrete right-of-way marker, S88°50'04"E 51.40'  
 Drill hole in top center of concrete right-of-way marker, N89°35'26"W 74.00'  
 "V" notch in top of metal guard rail post (ninth post north of bridge), N23°45'21"W 38.12'  
 Nail and tag #33142 in top of 6" x 8" wood post, N54°29'04"E 21.38'  
 Nail and tag #33142 in top of 6" x 8" wood post, N48°54'33"W 19.90'  
 (Bearings are based on 1951 plan centerline of M-129, which is N01°00'00"E at this location)



Signed by Keith R. Waters

Date 12-23-98

Surveyor's Michigan License No. 33142

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995