

JAN 21 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Mackinac County Remonumentation Corner

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T43N R1W T43N R1E	M-8 A-8 (Same corner Chippewa County)
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 30 1998

AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

ACCEPTED BY THE MACKINAC COUNTY,
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 11-20-98 NEH

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters, in a field survey on November 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 1/4 Corner Common to Section 24, T43N, R1W & Section 19, T43N, R1E

1840 - Original corner established by William A. Burt.

1991 - MDOT notes found 1/2" rebar and witnessed prior to road construction.

1992 - LCRC, liber 7, page 356, Chippewa County corner records. Neil E. Hill, P.S. 27447, found 1/2" rebar in monument box after road construction. Adjusted rebar to fit witnessed location and set cap #27447. Witnesses:
Nail and MDOT tag in power pole, N40°E 108.74'
Nail and MDOT tag in power pole, S70°W 78.95'
Concrete right-of-way marker, N85°E 72.35'
Nail and MDOT tag in fence post, S55°E 91.23'

1994 - LCRC, liber 8, page 316, Chippewa County corner records. Keith R. Waters, P.S. 33142, found a 1/2" rebar in a monument box and all witness objects as called for in 1992 LCRC.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Mackinac County Remonumentation Program.

Found a 1/2" rebar with cap #27447 in a monument box and all record witness objects as called for in 1992 and 1994 LCRC's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1/2" rebar with plastic cap #27447 in a monument box at the corner location, which falls in Highway M-129.
Witnesses:

Nail and MDOT tag in power pole (206), N40°E 108.74'
Nail and MDOT tag in power pole (E16), S70°W 78.95'
Masonry nail in top of concrete right-of-way monument, N85°E 72.35'
Nail and MDOT tag in fence post, S55°E 91.23'



Signed by Keith R. Waters

Date 12-23-98

Surveyor's Michigan License No. 33142