

JAN 21 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Mackinac County Remonumentation Corner

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T43N R1W T43N R1E	<b>M-9</b> A-9 (Same corner Chippewa County)
2. Property Controlling in Section	S T S T	R R R R
3. Miscellaneous Property in Sec.	S T S T	R R R R
4. Lot No.	Recorded Plat	
5. Private Claims		

RECEIVED & FILED  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

DEC 30 1998  
AM PM  
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 11-20-98 NEH

I, Keith R. Waters, in a field survey on November 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9 Corner Common to Secs. 24 & 25, T43N, R1W & Secs. 19 & 30, T43N, R1E

- 1840 - Original corner established by William A. Burt.
- 1947 - Corner location is shown on Michigan State Highway Plans, file # L-81-B-5.
- 1987 - LCRC, liber C-301, Mackinac County corner records. Neil E. Hill, P.S. 27447, found 1" square bolt in monument box. Witnesses: 8" Poplar, S80°W 51.14' - 1/2" Pipe @ culvert, N20°W 70.60' - Fence post, N80°E 73.31' - 3" Apple, S60°E 55.62'.
- 1987 - LCRC, liber 7, page 29, Chippewa County corner records. Neil E. Hill, P.S. 27447, same as above.
- 1991 - MDOT notes found corner and witnessed prior to road construction.
- 1992 - LCRC, liber 7, page 355, Chippewa County corner records. Neil E. Hill, P.S. 27447, found 1" square head bolt in a monument box, undisturbed after road construction. Witnesses: 8" Poplar, S80°W 51.14' - Power pole, S60°E 79.46' - Fence post, N70°E 72.94' - 4" Apple, S55°E 55.64' - "+" in S. end concrete culvert, N60°W 35.82'.
- 1994 - LCRC, liber 8, page 317, Chippewa County corner records. Keith R. Waters, P.S. 33142, found a 1" square head bolt in a monument box and all record witness objects as called for in 1992 LCRC.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Mackinac County Remonumentation Program. Found a 1" square head bolt in a monument box. Three of the record witness objects as called for in the 1992 and 1994 LCRC's are missing. Accepted corner as found and established additional witness objects

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1" square head bolt in a monument box at the corner location, which falls in Highway M-129. Witnesses:

- Nail and MDOT tag in power pole (213), S60°E 79.46'
- Nail and MDOT tag in fence post, N70°E 72.94'
- Nail and plastic tag #33142 in power pole (E7), S28°W 178.62'
- Nail and plastic tag #33142 in power pole (E8), N20°W 181.76'
- Nail and plastic tag #33142 in 4" balsam fir, WEST 46.56'

Signed by Keith R. Waters

Date 12-23-98

Surveyor's Michigan License No. 33142

