JAN 2 1 1999

SECTION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Mackinac County Remonumentation Corner

For corners in

4. Lot No.

5. Private Claims

Corner Code # Located in: Mackinac County M-10, T43N R1W 1. Public Land Survey A-10 (Same corner **T43N R1E** Chippewa County) Т R R 2. Property Controlling S T R Т in Section S R 3. Miscellaneous S Т S Property in Sec.

RECEIVED & FILED DIANE FRANKOVICH WACKING COUNTA SECURITY OF DEEDS

DEC 3 0 1998

ያለሳ 71819119111112111213141516

n

9 10

Register of Deeds Stamp & File Number

1


ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE

OFFICIAL CORNER UNDER PA. 345 OF 1990 AT A MEETING

HELD ON 11-20-98 NEW

I, Keith R. Waters, in a field survey on November 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

## M-10 1/4 Corner Common to Section 25, T43N, R1W & Section 30, T43N, R1E

1840 - Original corner established by William A. Burt.

. Recorded Plat

1947 - Corner location is shown on Michigan State Highway Plans, file # L-81-B-5.

1987 - LCRC, liber C-301, Mackinac County corner records. Neil E. Hill, P.S. 27447, found a 1/2" rod in concrete pavement, 4" below bituminous surface. Set monument box over found rod. Witnesses: 12" White pine, S65°E 75.20' - P. Pole, S50°E 80.94' - P.P. & T.P., WEST 72.49' - Fence post, S40°W 48.59'.

1987 - LCRC, liber 7, page 29, Chippewa County corner records. Neil E. Hill, P.S. 27447, same as above.

1991 - MDOT notes found and witnessed corner prior to road construction.

1992 - LCRC, liber 7, page 355, Chippewa County comer records. Neil E. Hill, P.S. 27447, found boat spike in a monument box after road construction, checked well with 1991 witnesses. Witnesses: P. pole, \$50°E 80.96' -P. pole, N85°W 72.37' - Conc. R.O.W. markers, S85°E 71.88' & N80°W 77.52' - 4" Cedar, N40°E 115.70'.

1994 - LCRC, liber 8, page 317, Chippewa County comer records. Keith R. Waters, P.S. 33142, found a boat spike in a monument box and all record witness objects from 1992 LCRC.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Mackinac County Remonumentation Program. Found a boat spike in a monument box and all record witness objects as called for in 1992 and 1994 LCRC's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a boat spike in a monument box at the corner location, which falls in Highway M-129. Witnesses:

Nail and MDOT tag in Power pole, S50°E 80.96' Nail and MDOT tag in Power pole, N85°W 72.37 Masonry nail in top of concrete right-of-way marker, S85°E 71.88' Masonry nail in top of concrete right-of-way marker, N80°W 77.52' Nail and plastic tag #33142 in 5" Cedar, N40°E 115.70'

ME OF MICHIGAN KEITH B. WATERS ¥ PROFESSIONAL SURVEYOR No. POFESSIONE 3

Keth R. U Et

12-23-98

Surveyor's Michigan License No. 33142

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975

REVISED OCT., 1995