

JAN 21 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Mackinac County Remonumentation Corner**

For corners in

Mackinac County

Located in:

Corner Code #

1. Public Land Survey

T43N R1W
T43N R1E

M-11
A-11 (Same corner
Chippewa County)

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGIST. OF DEEDS

DEC 30 1998
AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 11-20-98 WFH

I, Keith R. Waters, in a field survey on November 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 Corner Common to Secs. 25 & 36, T43N, R1W & Secs. 30 & 31, T43N, R1E

1840 - Original corner established by William A. Burt.

1991 - MDOT notes found a boat spike in a monument box and witnessed prior to road construction.

1992 - LCRC, liber 7, page 354, Chippewa County corner records. Neil E. Hill, P.S. 27447, found a boat spike in a monument box undisturbed after road construction. Checked well with 1991 witnesses. Witnesses:

- Nail and MDOT tag in Power pole, S40°E 104.51'
- Nail and MDOT tag in Power pole, S60°W 83.46'
- Tag west end gutter pan, N75°W 75.63'
- Stencil "+" in top center of concrete headwall, N50°E 41.33'

1994 - LCRC, liber 8, page 310, Chippewa County corner records. Keith R. Waters, P.S. 33142, found a boat spike in a monument box and all record witnesses as called for in 1992 LCRC.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Mackinac County Remonumentation Program.

Found a boat spike in a monument box and all record witness objects as called for in the 1992 and 1994 LCRC's, except for the gutter pan tag. Accepted corner as found and established an additional witness object.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a boat spike in a monument box at the corner location, which falls in the intersection of Highway M-129 and Rockview Road. Witnesses:

- Nail and MDOT tag in Power pole (E23), S40°E 104.51'
- Nail and MDOT tag in Power pole, S60°W 83.46'
- Stencil "+" in top center of concrete headwall, N75°W 75.63'
- Nail and plastic tag #33142 in Power pole, N20°W 164.23'



Signed by Keith R. Waters

Date 12-23-98

Surveyor's Michigan License No. 33142