

SURVEY &
REMONUMENTATION

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>43NR</u> <u>5W</u> | <u>E-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED & FILED
DIANE CRAIG, CLERK
MICHIGAN STATE BOARD OF DEEDS

DEC 07 1993

AM PM
7/6/93 10:00-10:15/1516

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Neil E. Hill

October 1 1993

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845: Corner positions were established H. Brevoort, Jr., D.S., in the original G.L.O. survey and the original G.L.O. subdivision survey of T43N, R05W; Used a 18" Sugar Maple as the corner position. Established the following references:
24" S. Maple S33E 50 links 18" S. Maple S20W 23 links

1990: The USDA Forest Service found no other record of any subsequent corner restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1990: The USDA Forest Service found no original or any subsequent corner evidence. Corner position was re-established by survey on line at the proportionate measured position on line between the Southwest Corner and the South Quarter Corner of Section 33, T44N, R05W.

1990: The USDA Forest Service set a 1/2" by 18" long rebar with a plastic I.D. cap, buried approximately 0.5 feet below road surface. Established the following references of which the Bearing Trees are blazed, scribed, painted, and tagged:
Utility pole N19E 99.4 feet Utility pole S08E 250.2 feet
GLD monument J2/33 N90W 31.12 feet Utility pole N59W 276.4 feet
Post w/sign N90W 15.0 feet


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Found a 1/2" rebar with a plastic I.D. cap, buried approximately 0.5 feet below road surface, and verified 1990 witnesses. Additional reference established:
3 feet West of the centerline of N-S gravel road, 63 feet South of the centerline of a gravel road West, 29 feet South of a fence line East.

1993: Replaced with 5/8" X 30" rod with 3" diameter aluminum cap. Upon review, the location and witnesses for the corner as recorded in Liber D-0127 (Corner Records), are sufficient to perpetuate the corner location.

igned by Neil E. Hill P.S. P.C.

urveyor's Michigan License No. 27447



Date October 15, 1993

Remonumentation Surveyor

D-0234

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983