

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 43NR 5W E-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED & FILED
DIANE P. HAYDON
MICHIGAN STATE BOARD OF DEEDS

DEC 07 1993

AM PM
7[8]9[0] 1[0] 1[0] 1[0] 1[0] 1[0]

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 3.

Neil E. Hill October 1 93

I, Neil E. Hill, in a field survey on October 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845: Corner positions were established H. Brevoort, Jr., D.S., in the original G.L.O. survey of T43N, R05W. Used a 36" Birch as the corner position, no references established.
1990: The USDA Forest Service found no other record of any subsequent corner restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1990: The USDA Forest Service found no original or any subsequent corner evidence. Corner position was re-established by survey at the point of intersection of centerlines of County Road 530 and County Road 535.
1990: The USDA Forest Service set a 1/2" by 18" long rebar, capped with a plastic I.D. cap. Top of rebar is flush with road surface. Established the following references of which the Bearing Trees are blazed, scribed, painted, and tagged:
Utility pole (Guy Pole) N40E 48.2 feet Utility pole EK3 2971 S80E 251.2 feet
Utility pole (Guy Pole) S43W 48.0 feet Utility pole EK3 294 N38W 48.5 feet
Post w/sign S10W 48.0 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Found a 1/2" rebar, capped with a plastic I.D. cap and verified 1990 witnesses. Established additional references:
Utility pole (Guy Pole) EK3 294Y N40E 48.2 feet
Utility pole (Guy Pole) EK3 294X S43W 48.0 feet
Found 0.6 North of bituminous road centerline, Westerly track of road North, in line with fence and tree line South.
1993: Replaced with 5/8" X 30" rod with 3" diameter aluminum cap. Upon review, the location and witnesses for the corner as recorded in Liber D-0130 (Corner Records), are sufficient to perpetuate the corner location.

Signed by Neil E. Hill P.S. P.C.
Surveyor's Michigan License No. 27447



October 15, 1993

Remonumentation Surveyor

D-0236