

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 43NR 5W G-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

RECEIVED & FILED
REGISTERED CLERK
DEC 07 1993
Register of Deeds Stamp & File Number

Neil E. Hill October 1 93

I, Neil E. Hill, in a field survey on October 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column G and row 2.

A. Description of original monument and accessories and/or subsequent restoration:

1845: Corner positions were established H. Brevoort, Jr., D.S., in the original G.L.O. survey of T43N, R05W. Set a wood post and established the following references: 12" S. Maple S08E - 22 links 8" S. Maple S04W - 46 links

1990: The USDA Forest Service found no other record of any subsequent corner restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1990: The USDA Forest Service found no original or any subsequent corner evidence. Corner position was re-established by survey; using the existing evidence of the old cemetery which is South and West of this corner.

1990: The USDA Forest Service set a 1/2" by 18" long rebar, capped with a plastic I.D. cap. Top of rebar is approximately 0.5 feet below road surface. Established the following references of which the Bearing Trees are blazed, scribed, painted, and tagged: Utility pole S17E 155.7 ft. 12" S. Maple S38W 50.1 ft. 10" S. Maple N11W 104.6 ft. Post w/sign N90W 12.0 ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Found a 1/2" rebar, with a plastic I.D. cap. Top of rebar is approximately 0.5 feet below road surface. Established the following references of which the Bearing Trees are blazed, scribed, painted, and tagged: Utility pole S17E 155.7 ft. 12" S. Maple S38W 50.1 ft. 10" S. Maple N11W 104.6 ft. Post w/sign N90W 12.0 ft.

1993: Replaced with 5/8" X 30" rod with 3" aluminum cap. West edge of a gravel road, 12' West of a gravel road centerline Upon review, the location and witnesses for the corner as recorded in Liber D-130 (Corner Records), are sufficient to perpetuate the corner location.

Signed by Neil E. Hill P.S., P.C.
Surveyor's Michigan License No. 27447
Remonumentation Surveyor

Date October 15, 1993
Circular seal: NEIL E. HILL, REGISTERED LAND SURVEYOR, No. 27447
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971, REVISED MAY 14, 1975, REVISED JAN., 1983

D-0238