

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Mackinac Co. 3 Corners.

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> N. <u>X</u> , R. <u>6</u> W. <u>X</u>	C-11, F-7, E-9
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Billy D. Buckler**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7/21 & 7/25, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
All corners set by H. Brevoort Jr., D.S. in 1845.

C-11 Sec. Cor. 29-30-31-32. Bearings were: Pine 16, N80°E, 16 lks. Pine 22, N41°W, 20 lks.	F-7 $\frac{1}{4}$ Cor. bet. Sec's. 16-21. Bearings were: Cedar 5", N12°E, 18 lks. Birch 3", S12°E, 20 lks.	E-9 Sec. Cor. 20-21-28-29. Bearings were: Tam. 12", N16°W, 14 lks. Balsam 4", N62°E, 14 lks.
---	---	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11** Placed corner by proportionate measure bet. corners, 1 mile North and 1 mile South, and at record distance from corners to East. Found a cedar with blaze facing the corner. 4' North of corner. Many pines but none could be identified.
- F-7** Replaced corner from possible original witness; a cedar stub with rotted out faces in proper position. Checks well with corners to East and West.
- E-9** Found several lines of old blazes from 40 yrs. to 75 yrs. old. Found no evidence of corner or witnesses. I seriously doubt if the surveyor was actually at this corner. Site is heavy cedar, some tamarack and Spruce. Record indicates a 4" Balsam. Corner placed in line of 75 yrs. old blazes to E-W and at record distance from East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at all corners.

C-11 New Bearings: 24" W. Pine, N43°W, 37.8' 16" W. Pine, S9°E, 23.0' 28" W. Pine Stump, East, 18.0'	F-7 New Bearings: 7" Soft Maple, N15°W, 25.9' 4" Soft Maple, S20°W, 27.1' 6" B. Spruce, S88°E, 9.7' Corner lies 50' South of woods Road.
E-9 New Bearings: 7" Cedar, S58°E, 2.7' 7" Cedar, S59°W, 21.7' 7" Cedar, N32°E, 13.6'	

SIGNED BY Billy D. Buckler DATE 9/19/77
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)