

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Mackinac Co. 3 Corners.

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 N. R. 6 W. x	K-3, K-10, C-6
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. , RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey 9-14, 15, 16-, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corners set by H. Brevoort, Jr., D.S. in 1845 and 1849.

K-3 Sec. Cor. 1-2-11-12. Bearings were: Balsam 6, N16°E, 26 lks. Cedar 14, N17°W, 36 lks.	K-10 $\frac{1}{4}$ Cor. Bet. Sec's. 25-26. Bearings were: Hemlock 12, S7°W, 44 lks. Hemlock 12, S8°E, 58 lks.	C-6 $\frac{1}{4}$ Cor. Bet. Sec's. 17-18. Tam. 4" for corner tree. No other line tree near.
---	--	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-3** Replaced corner as found by Marcus Schaaf, R.L.S. in 1937. Position checks with streams North, South, East and West.
- K-10** Re-witnessed corner found by Marcus Schaaf, R.L.S. in 1937. Found 1½" iron pipe set by Schaaf, by prop. measure. Found witnesses also by Schaaf.
- C-6** Re-established corner at record distance from corner ½ mile North. Found no evidence of original corner. Found old timber which should have existed when original survey was in progress.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at corners K-3 and C-6. Re-witnessed K-10 corner.

K-3 New Bearings: 30" W. Pine Stump, S49°E, 27.5'. No others available.	K-10 New Bearings: 8" R. Pine, S7°E, 11.4' 12" R. Pine, N47°W, 34.8'	C-6 New Bearings: 10" Cedar, S17°W, 46.0' 12" Cedar, N84°E, 31.5' 4" Spruce, N50°W, 11.2'
---	---	---

SIGNED BY: Billy D. Buckler
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 9/19/77



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____