

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 N. R. 6 W.	G-7, G-9, G-11
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on (G-7, 7/21/77) 7/18, 19 77, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corners set by H. Brevoort, Jr. D.S. in 1845.

G-7 Sec. Cor. 15-16-21-22 Bearings were: Cedar 10", S18°W, 25 lks. Cedar 10", S71°E, 14 lks.	G-9 Sec. Cor. 21-22-27-28 Bearings were: Maple 12", N67°E, 27 lks. Birch 10", S42°E, 20 lks.	G-11 Sec. Cor. 27-28-33-34 Bearings were: Cedar 10, N34°W, 16 lks. Cedar 8, S29°E, 26 lks.
--------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-7 Corner re-established at record distance from corner $\frac{1}{2}$ mile South and at record distances to stream crossings, South 1.50 Chs.; East 2.00 Chs.; North 8.50 Chs. and West 3.10 Chs. Numerous Cedar stumps, all badly burned and rotted.

G-9 Found old line of blazes to East and West of corner, aprox. 55 years old. No evidence of original witnesses. Corner re-established on East-West blaze line and at record distance, East $\frac{1}{2}$ mile to corner.

G-11 Re-established corner at intersection of old blaze lines, aprox. 55 years old. position checks well for distance East 1 mile and a corner $\frac{1}{2}$ mile South. Green Cedar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" aluminium cap at corners.

G-7 New Bearings: 5" Cedar, S87°W, 14.8' 7" Cedar, N35°E, 27.4'	G-9 New Bearings: 14" Cedar, S44°W, 40.0' 12" Cedar, S60°E, 37.5'	G-11 New Bearings: 8" Cedar, S50°E, 2.5' 6" Cedar, N10°W, 7.3' 6" Cedar, S60°W, 5.5'
------------------------------------------------------------------------------	--------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------

SIGNED BY Billy D. Buckler
 Billy D. Buckler

DATE 9/7/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____