

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43-44 N.R. 6 W.


Chippewa-Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 3, 4, 33, 34

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/19/63

WITNESSES TO CORNER..... 10" Cedar (S. 34 N.B.T.) N. 76° E., 69 Lks.



16" Hemlock (S. 3 N.B.T.) S. 28° E., 37 Lks.

5" Soft Maple (S. 33 N.B.T.) N. 39° W., 34 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by single proportionate measure along township line from good corners 3 miles East and 1 mile West.

SURVEYOR'S SEAL

SIGNED Billy O. Buckles DATE 1/27/64  
REGISTERED LAND SURVEYOR