

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 N.R. 6 W.


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for North side Section 5

CORNER MONUMENT 1" iron pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9-19-63

WITNESSES TO CORNER..... 8" S. Maple (in clump) (1/4 S.) (B.T.) S. 87° W., 28 Lks.



CIRCLE CORNER REGISTERED

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed Midway and on Line between Closing Corners 1/2 mile to East and West.

Note: Corner lies 35½ Lks. East of South 1/4 Corner of Section 32, T. 44 N., R. 6 W.

SURVEYOR'S SEAL

SIGNED Billy E. Buckles DATE 4/27/64  
REGISTERED LAND SURVEYOR