

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 6 W


Mackinac COUNTY

DESCRIPTION OF CORNER Closing Corner for Sections 4 and 5

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 10/18/60 Shown by Forester Halbach

WITNESSES TO CORNER.....12" Cedar (CC S 4 NBT) S 58° E 7 1/2 Links



14" Hemlock (CC S 5 NBT) S 60° W 57 1/2 Links

AND

CIRCLE CORNER, REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from 12" Yellow Birch, S 39° W, 33 Links which has faces and possible iron marks on upper face. Old Blases in vicinity. This corner lies 20 links East of corner for Sections 32, and 33, T 44 N, R 6 W.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE

4/27/61