

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

3 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>X</u> S. R. <u>6</u> W.	<u>M-2, M-3, K-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10/6 & 9/23, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-2 Quarter corner on East side, Sec. 1, set by Wm A. Burt, D.S. in 1840. Bearings were: Y. Pine 8", for Quarter Cor. and Y. Pine 12", N12°W, 26 lks.
- M-3 Sec. Corner, Sec's 1-12 on East boundary of Twp., set by Wm A. Burt, D.S. in 1840. Bearings were: Hemlock 18", S12°W, 32 lks and Spruce 10", N12°W, 13 lks.
- K-13 Sec. Corner bet. 35-36 on South boundary of Township, set by Austin Burt, D.S. in 1840. Bearings were: Beech 8", N48°E, 45 lks and Fir 7", North, 25 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- M-2 Re-established corner by single proportionate measure along Range Line, bet. two Section Corners. Found no evidence of original corner.
- M-3 Re-established corner by single proportionate measure along Range Line. Found no acceptable evidence of original corner.
- K-13 Re-established corner by single proportionate measure along Township Line. Found no evidence of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at all corners.

- | | | |
|--|---|--|
| <p><u>M-2</u> New Bearings:
 7" Red Pine, N19°W, 43.0'
 8" Jack Pine, S39°W, 14.0'
 8" Jack Pine, S44°E, 18.0'</p> | <p><u>M-3</u> New Bearings:
 9" Twin S. Maple, N50°W, 29.9'
 8" B. Spruce, S39°W, 15.5'
 8" B. Spruce, S52°E, 13.1'</p> | <p><u>K-13</u> New Bearings:
 14" R. Pine, N33°W, 41.1'
 4" J. Pine, N42°E, 42.7'
 8" J. Pine, S42°E, 30.1'
 Corner lies 30' SE of Pine plantation corner.</p> |
|--|---|--|

SIGNED BY Billy D. Buckler DATE 10-78
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____