

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Maekinae Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. <u>X</u> , R. <u>6</u> E. <u>W</u> .	<u>D-5</u> <u>E-4</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-4, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corners set by H. Brevoort Jr., D.S. in 1845.

- D-5** Quarter Corner between Sec's. 8-17, bearings were: Cedar 6, N88°W, 4.65 chs. and Tamarack 6, S89°W, 5.72 chs.
- E-4** Quarter Corner between Sec's. 8-9, bearings were: Cedar 3, N28°E, 16 lks. and Tamarack 4, N67°W, 29 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-5** Restored Corner midway and on line between two Section Corners.
- E-4** Restored Corner midway between two Section Corners.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at both corners.
- D-5** New Bearings: 8" Tamarack, S56°W, 26.7' and 12" Tamarack, N64°W, 40.5'.
- E-4** New Bearings: 12" Spruce, S18°W, 42.0' and 6" Spruce, S62°W, 35.7'.

SIGNED BY Billy D. Buckler
Billy D. Buckler

DATE 2-16-79

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____