

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Mackinac Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>X</u> , R. <u>6</u> W.	<u>H-7</u> <u>J-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-27, 19 78, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corners set by H. Brevoort Jr., D.S. in 1845.

**H-7** Quarter Corner between Sec's. 15-22, bearings were: Maple 8, S61°E, 19 lks. and Beech 12, N56°W, 27 lks.

**J-5** Quarter Corner between Sec's. 11-14, bearings were: A Cedar 10" marked for the Quarter Post.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**H-7** Corner restored on line and midway between two Section Corners. No evidence of original corner.

**J-5** Corner restored midway and on line between two Section corners.


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" pipe with 4" aluminium cap at both corners.

**H-7** New Bearings: 12" S. Maple, N18°W, 20.7' & 8" S. Maple, S33°W, 9.4' & 6" S. Maple, S89°E, 14.35'.  
Corner lies 70' West of an old N-S road.

**J-5** New Bearings: 14" W. Birch, N57°E, 32.2' and 4" Spruce, S5°E, 25.1'.

SIGNED BY Billy D. Buckler DATE 2-16-79  
Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_