

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>6W</u>	<u>L1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 08 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(L1) Corner common to Section 36 T44N-R06W and Section 1 T43N-R06W. 1963: Billy D. Buckler RLS reestablished the corner by single proportionate measurement along the township line. 1" pipe with 4" aluminum cap. 9" B.Spruce S32W 46 links, 11" J.Pine S45E 88 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L1) Recovered the 1963 monument in good condition and at record bearing and distance from the remains of the 1963 NBTs. The J. Pine is a stump with scribing visible. The B.Spruce is a stump, cut low, with no marks visible. Left the monument in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L1) Fd. 1" ID iron pipe with 4" alum. State of Mich. cap. Blazed, scribed, and set measuring nails in:
 6" Balsam S47W 42.5' "1/4S NBT"
 5" B.Spruce S41E 22.25' do
 5" B.Spruce N80E 10.7' do
 3" J.Pine N43E 32.1' do
 Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 11/28/01