

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 6W	E6
	T 43N R 6W	C5
	T	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E6 06/24/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E6) Quarter corner common to Sections 16 and 17. Remonumented in 1961 by Billy D. Buckler RLS: This corner was replaced from W.Pine stump bearing S73W, 82 links (possible bearing tree). Found old blazes to North, South, and West. Distance north to stream 3.00 chains check good. Corner lies 4 chains East of Road, placed location post on road. Set 1" pipe with 4" brass cap. 8" Cedar N85W 08.5 links, 8" Cedar S28E 43.5 links.

(C5) Corner common to Sections 7-8-17-18. 1977 - Corner reestablished by Billy D. Buckler RLS: Reestablished corner facing an old face on a Hemlock tree. Appears to be on an old blazed line North South. Found no evidence of corner. Corner lies approx. record distance from corners to East. Set 1" pipe with 4" aluminum cap. 6" Maple N19W 32.5', 10" Maple S37W 19.2', 10" Maple S24E 19.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E6) Found the 1961 monument in good condition and at record bearing and distance from the 1961 NBT Cedar NW, in good condition. The NBT Cedar SE is still in place but accurate measurement to it was obstructed by a windfall. It appears to be at record bearing and distance. Accepted the monument as the best available evidence of the position of the corner.

(C5) Found the 1977 monument in good condition and at record bearing and distance from the 1977 witness trees, all in good condition. Left the monument in place and made one new witness. The corner is being recorded in order to update the accessories. The undersigned did not use this position to establish subdivisional or property controlling corner positions at this time.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E6) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 11" Cedar N81W 5.88' mrkd "1/4S" 1961 NBT
 11" Tamarack S78E 24.02' mrkd "1/4S NBT"
 7" Spruce N18W 11.88' do
 11" Cedar S68W 22.89' do
 Bearings are magnetic.

(C5) Found 1"pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Maple N20W 32.36' mrkd "S7" 1977 NBT
 14" Maple S38W 19.62' "S18" do
 14" Maple S22E 19.65' "S17" do
 7" Maple S77W 14.32' mrkd "S18 NBT"
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 02/17/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

