LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac		Located in:	Corner Code ##
	(County)	Coodied III.	Owner Code
1.	Public Land Survey	T 43N R 7N	F12
		T R	
		T B	
		T R	
2.	Property Controlling	S _33 T _43N R _7N	<u>HC 8-4</u>
	in Section	S <u>33</u> T <u>43N</u> R <u>7N</u>	WC F12-5
3.	Miscellaneous	· S T R	

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

Property in Sec.

Private Claims

March 02, 1992 I, Stephan J. Szyszkoski , in a field survey on _ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F12) Corner previously recorded by Billy B. Buckler in 1963 as being established and monomented at the intersection of 1/4 lines. (MC 8-4) Southwest corner of the Morth B Chains of the Southeast quarter of the Morthwest quarter of Section 33. Corner not established in original survey. Found no record of prior monumentation.

(MC F11-F12) Southeast corner of the North 8 chains of the Southeast quarter of the Northwest quarter of Section 33. Not established in original survey. Found no record of prior monumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F12) Found and accepted 1° pipe with 4° tablet set by Buckler with both of his 1963 BT's agreeing.

(NC 8-4) Established corner on west N-S 1/16 line 528.02' south (8 chains perpendicular to the morth E-N 1/16 line) of the unconsented NW 1/16 corner of Section 33.

(NC F31-F12) Established corner on N-S 1/4 line of section 33 528.02' (being 8 chains as measured perpendicular to north E-M 1/16 line) southerly of north 1/16 corner. Found no monumentation at this position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(Fi2) Found 1" pipe with 4" cast (MC 8-4) Set a 1"x32" painted iron pipe (MC F11-F12) Set 1"x32" painted iron aluminum tablet. S75E 0.9° set mail and tag in 20" W. Pine (obt); \$30E 4.25" nail and tag in 5" spruce; \$30M 21.17' set mail and tag in 18" W. Pine (obt); M30N 17.7' mail and tag in 9" maple. scribed obt's at BH. Blazed and scribed others at BN and base.

with 4" cast aluminum HDMR tablet. MS&E 9.9' nail and tag in 11" maple: \$88E 32.1' nail and tag in 10" maple; \$350 7.8' nail and tag in 9" maple; 9559 13.7' nail and tag in 7" maple. Blazed and scribed all trees at BH ("PC") and hase ("RT").

pipe with 4° cast aluminum HBMR tablet. NIGE 12.2' mail and tag in 13" W. Pine; S60E 22.7' nail and tag in 12" W. Pines S48W 5.7' nail and tag in 6" W. Pine: M44W 34.25' mail and tag in 11" W. Pine. All trees blazed and scribed at DH ("PC") and base ("BT"). of Mich

LAND SURVEYOR No.

STEPHAN J. SZYSZKOSKI