

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 R.R. 7 & 8 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner for T43N R8W ^{24/19}/_{25/30} T43N R7W

CORNER MONUMENT 1" Iron Pipe with 1/2" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/20/66, Frank J. Bray

WITNESSES TO CORNER..... 8" R. Pine (S19)(NBT) N 23° E, 30 Links



8" R. Pine (S30)(NBT) S 27° E, 11 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and the single proportioned measurement between section corners 1 mile to north and to south.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/28/67
REGISTERED LAND SURVEYOR