

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 7W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner for Sections ^{16/15} 21/22

CORNER MONUMENT 1" Iron Pipe with 1/4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/15/66, Frank J. Bray

WITNESSES TO CORNER..... 12" Cedar (S15)(NBT) N 70° E, 23 1/2 Links



14" Cedar (S21)(NBT) S 03° W, 11 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was reestablished by double proportionate measurement between Section Corner 1 mile to North, Section Corner 2 miles to East and 1/4 corners 1/2 mile to South and West. Blazes in vicinity but no original evidence.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/19/67
REGISTERED LAND SURVEYOR