

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 7W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 15/14

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/16/66, Frank J. Bray

WITNESSES TO CORNER..... 8" Cedar (1/4S)(NBT) N 04° E, 18 Links



6" Cedar (1/4S)(NBT) S 80° E, 05½ Links

(14" W. Pine (1/4S) possibly original) N 72° E, 87 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between Section corners 1/2 mile to North and to South. Pine with scribe marks faces corner as set. This may have been an extra BT. Not noted in original field notes.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/25/67  
REGISTERED LAND SURVEYOR