

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

5 Corners.

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---|--|-----------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>43</u> N. X , R. <u>7</u> X W. | H-2, G-2, G-1 |
| 2. PROPERTY CONTROLLING IN SECTION <u>3</u> | , T. <u>43</u> N. X , R. <u>7</u> X W. | 12-Sec.3 12A-Sec.3 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ N. _____, R. _____ E. _____ S., R. _____ W. | |
| 4. LOT NO. _____ | , RECORDED PLAT _____ | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-29 & 12-5, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- H-2 Center Corner of Section 3, T43N R7W.
 - G-2 Quarter Corner bet. Sec's. 3-4, set by H. Brevoort Jr. D.S. in 1845.
Bearings were: Beech 10", S74°W, 16 lks. & Beech 14", S67°E, 19 lks.
 - G-1 Closing corner bet. Sec's. 3-4, set by H. Brevoort Jr. D.S. in 1845.
Bearings were: Sugar 14", S37°W, 24 lks. & Beech 10", S2½°E, 22 lks.
 - 12-Sec.3 South 1/16 Corner of Section 3, T43N R7W.
 - 12A-Sec.3 1/64 Corner North of South 1/16 Corner of Section 3 T43N R7W.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- H-2 Placed corner at intersection of lines connecting opposite ¼ Corners.
 - G-2 Re-established corner in Center of North-South road and 33.0' South of Fence Line, on South side of Cemetery.
 - G-1 Re-established corner 30.4' West of Corner 33-34, T44N R7W; on Township Line.
 - 12-Sec.3 Placed corner midway and on line bet. ¼ Cor. South and Center Cor. North.
 - 12A-Sec.3 Placed corner midway bet. North 1/16 corner and the center corner, Sec. 3, T43N R7W.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Placed 1" pipe with 4" aluminum cap at all corners except G-2 and G-1.
- H-2 Bearings: 6" R. Pine, S11°W, 15.4' and 6" R. Pine, N70°E, 9.3'.
 - G-2 Buried ½" x 16" Iron in center of road.
New Bearings: 15" Hard Maple, N76°W, 49.9' and 10" Hard Maple, N87°E, 45.9'.
 - G-1 Set Iron Pipe in 3" Drill Hole in limestone rock.
Corner is 30.4' West of Section Corner 33-34 T44N R7W on The Township Line.
 - 12-Sec.3 Bearings: 16" R. Pine, N65°W, 16.8' and 16" R. Pine, S65°E, 17.4'.
 - 12A-Sec.3 Bearings: 16" J. Pine, N50°E, 17.3' and 8" J. Pine, S77°W, 32.1'.

SIGNED BY Billy D. Buckler DATE 1-27-77
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____